

- 1. STEEL CASING SHALL BE INSTALLED USING THE BORE, JACK AND/OR TUNNEL METHOD.
- 2. FULL PENETRATING WELDS SHALL BE USED TO JOIN CASING SECTIONS
- 3. CASING SPACERS SHALL BE INSTALLED AT 5 FT. INTERVALS OR AS RECOMMENDED BY THE PIPE MANUFACTURER. IN ANY CASE MINIMUM JOINT DEFLECTION SHALL BE OBSERVED.
- 4. CARE SHALL BE EXERCISED DURING INSTALLATION IN ORDER TO PREVENT DAMAGE TO PIPE AND BELL.
- 5. CONTRACTOR SHALL FOLLOW PIPE INSTALLATION PROCEDURES AS DETAILED BY THE PIPE MANUFACTURER.

